



NEW WESTMINSTER

September 22, 2016

ADDENDUM #2
NWIT-16-20
2016 Watermain Replacement and Flowmeter Installation
New Westminister, BC

This addendum modifies the Invitation to Tender only as noted:

FORM OF TENDER

Appendix A – Schedule of Quantities and Prices

<DELETE> Appendix A – Schedule of Quantities and Prices

<REPLACE WITH> Appendix A – Schedule of Quantities and Prices Addendum 2 (3 Pages following)

SUPPLEMENTAL SPECIFICATIONS

Section 16470 Kiosk

1.5 Approved Suppliers

<ADD>

1.5.1.4 PLC Technical Services Ltd – Surrey, BC

DRAWINGS

Drawing W09 Ash Street, Watermain Replacement

<CORRECTION> **Drawing W09 West-End Tie-In Plan**

The tie-ins should be with 45 degree bends and with the old main abandoned. The IFC drawings will be corrected as follows:

Delete material call out for tie-in and replace with:

1 – 200 dia TY X TY 45 degree BEND c/w THRUST BLOCK (END BEARING AREA 0.3m²)

1 – 200 dia DI STUB TO SUIT

1 – 200 dia TY X TY 45 degree BEND c/w THRUST BLOCK (END BEARING AREA 0.3m²)

1 – 200 dia DI STUB TO SUIT

1 – 200 dia TY X 150 dia TY REDUCER

1 – 150 dia DI STUB TO SUIT

1 – 150 dia MECH COUPLING

East of the tie-in, the existing 150 mm watermain shall be abandoned and plugged.

NWIT-16-20
Addendum #2
September 22, 2016

Drawing W11 Fourth Street, Watermain Replacement
<CORRECTION> Drawing W11 for the West-End Tie-In at Eighth Street

Delete material call out for tie-in and replace with:

- 1 – 200 dia TY X TY 45 degree BEND c/w THRUST BLOCK (END BEARING AREA 0.3m²)
- 1 – 200 dia DI STUB TO SUIT
- 1 – 200 dia TY X TY 45 degree BEND c/w THRUST BLOCK (END BEARING AREA 0.3m²)
- 1 – 200 dia DI STUB TO SUIT
- 1 – 200 dia TY X 150 dia TY REDUCER
- 1 – 150 dia DI STUB TO SUIT
- 1 – 150 dia MECH COUPLING

East of the tie-in, the existing 150 mm watermain shall be abandoned and plugged.

Please acknowledge this addendum as directed in the Form of Tender.

END OF ADDENDUM #2

Yours truly,



Heather M. Rossi
Intermediate Buyer

FORM OF TENDER – Appendix 1**SCHEDULE OF QUANTITIES AND PRICES**

(See paragraph 5.3.1 of the Instructions to Tenderers - Part II)

(All prices and *Quotations* including the *Contract Price* shall include all *Taxes*, but shall not include *GST*. *GST* shall be shown separately.)

Item	Description	Unit	Quantity	Unit Price	Amount
SECTION 1 – Water Works – Ash Street					
1.1	S&I 200 dia. D.I. Watermain Station 0+000 to 0+248 and branches	lm	276	\$	\$
1.2	Fourth Ave. Tie-in Complete	L.S.	N/A	N/A	\$
1.3	Third Ave. Tie-in Complete	L.S.	N/A	N/A	\$
1.4	Walmsley Tie-in Complete	L.S.	N/A	N/A	\$
1.5	Joint Restraint at Intersections	L.S.	N/A	N/A	\$
1.6	Water Service Connections (19 dia.) Including Water Meter Box	Each	14	\$	\$
1.7	Water Service Connections (38 dia.) Including Water Meter Box	Each	1	\$	\$
1.8	Water Service Connections (51 dia.) Including Water Meter Box	Each	1	\$	\$
1.9	Water Service Connections (150 dia.) Including Water Meter Box	Each	1	\$	\$
1.10	Supply and Install Complete Hydrant Assembly	Each	2	\$	\$
1.11	Permanent Pavement Restoration	tonnes	100	\$	\$
TOTAL SECTION 1					\$
SECTION 2 – Water Works –Seventh Street					
2.1	S&I 200 dia. DI Watermain Station 0+00 to 0+221and branches	lm	288	\$	\$
2.2	Blackford St. Tie-in Complete	L.S.	N/A	N/A	\$
2.3	Walmsley St. Tie-in Complete	L.S.	N/A	N/A	\$
2.4	Third Ave Tie-in Complete	L.S.	N/A	N/A	\$
2.5	Joint Restraint in Intersections	L.S.	N/A	N/A	\$
2.6	Supply and Install Complete Hydrant Assembly	Each	2	\$	\$

Item	Description	Unit	Quantity	Unit Price	Amount
2.7	Water Service Connections (19 dia.) including water meter box	Each	5	\$	\$
2.8	Permanent Pavement Restoration	tonnes	105	\$	\$
TOTAL SECTION 2					\$
SECTION 3 – Water Works –Fourth Avenue					
3.1	S&I 200 dia. DI Watermain Sta-0+000 to 0+197 and branches	lm	233	\$	\$
3.2	Eighth Street Tie-in Complete	L.S.	N/A	N/A	\$
3.3	Seventh Street Tie-in Complete	L.S.	N/A	N/A	\$
3.4	Joint Restraint at Intersections	L.S.	N/A	N/A	\$
3.5	Water Service Connections (19 dia.) Including Water Meter Box	Each	4	\$	\$
3.6	Water Service Connections (102 dia.) including water meter box	Each	1	\$	\$
3.7	Supply and Install Complete Hydrant Assembly	Each	1	\$	\$
3.8	Permanent Pavement Restoration	tonnes	80	\$	\$
TOTAL SECTION 3					\$
SECTION 4 –First Street Meter					
4.1	S&I Meter Chamber, Insertion Meter, Kiosk, Conduit, Wiring, Antennae and All Appurtenances watermain	L.S.	N/A	N/A	\$
4.2	Permanent Pavement Restoration	tonnes	4	\$	\$
TOTAL SECTION 4					\$

FORM OF TENDER – Appendix 1

SCHEDULE OF QUANTITIES AND PRICES

(See paragraph 5.3.1 of the Instructions to Tenderers - Part II)

(All prices and *Quotations* including the *Contract Price* shall include all *Taxes*, but shall not include *GST*. *GST* shall be shown separately.)

TENDER SUMMARY

SECTION		TOTAL AMOUNT
SECTION 1 – Water Works – Ash Street		\$
SECTION 2 – Water Works – Seventh Street		\$
SECTION 3 – Water Works – Fourth Avenue		\$
SECTION 4 – Water Works – First Street Meter		\$
TENDERED PRICE		\$
5% GST		\$
TOTAL TENDERED PRICE		\$