



# NEW WESTMINSTER

September 22, 2016

**ENQUIRIES AND RESPONSES #2**  
**NWIT-16-20**  
**2016 Watermain Replacement and Flowmeter Installation**  
**New Westminster, BC**

**ANSWERS TO SUBMITTED QUESTIONS**

- Q1 On Ash Street northwest of Fourth Ave. at the tie in and on Ash Street southeast of Third Ave. at the tie in – the fittings shown connecting to the existing main are “wyes” – this will connect to the abandoned section of the watermain pipe along with the live section of the existing main plus the live new main. Do you want to connect to the main that is to be abandoned?? This fitting should be a 45 degree bend plus coupling ONLY. This scenario is also at the tie in point at Fourth Ave. & Eighth Street – is this what you want?
- A1 [Refer to Addendum #2 for revisions to Drawings.](#)
- Q2 The new watermain services shown on the drawings appear to be larger than 19 mm, is this to paid as an extra to the contract.
- A2 [We are aware of four services with larger diameters. Please refer to Addendum #2 for a Revised Schedule of Quantities and Prices.](#)
- Q3 Are there any working hour restrictions for any roads?
- A3 [Standard working hours for all streets except Eighth Street. Work in the intersection of Eighth Street and Fourth Avenue is restricted to between 9:00 am and 3:00 pm.](#)
- Q4 Can you please provide a link for the City Supplementary Drawings & Specifications on the website.
- A4 [The link is on the Planning, Building and Development section under “Subdivision Process” <https://www.newwestcity.ca/database/rte/files/Schedule%20C-Supplementary%20Specifications%20and%20Detail%20Drawings.pdf>](https://www.newwestcity.ca/database/rte/files/Schedule%20C-Supplementary%20Specifications%20and%20Detail%20Drawings.pdf)

Yours truly,

Heather M. Rossi  
Intermediate Buyer