



# NEW WESTMINSTER

September 19, 2023

**ADDENDUM #2  
NWIT-23-18  
SA-16 Sanitary Lift Station Upgrades  
New Westminster, BC**

This addendum modifies the Invitation to Tender only as noted:

**FORM OF TENDER – APPENDIX 1**

<DELETE>

Appendix 1 Schedule of Quantities and Prices included with Tender Document (4 pages) and

<REPLACE WITH>

Appendix 1 Schedule of Quantities and Prices Revised Addendum #2 changes highlighted yellow (4 pages following)

**PROJECT SPECIFIC SPECIFICATIONS 01 43 00**

**Section 01 43 00 MEASUREMENT AND PAYMENT**

<ADD>

**“Item 7.05 Additional Cost for Removal and Disposal of Contaminated Materials in the Existing Pump Station Building (Provisional)”**

This item includes all additional costs for the safe removal and disposal of contaminated materials identified at the existing SA-16 Sanitary Pump Station, and to be identified in a Hazardous Materials Report prepared by the owner.

Any *additional* costs for the safe removal and disposal of contaminated material will be paid at the cost to the contractor plus 10%. This does not include the cost of transportation.”

**CLARIFICATIONS**

Access hatch Access hatches to have checker plate tread plates, no additional slip resistance product required on hatch surface. All access hatches to come with trough frames with odour reducing gaskets. No additional structural engineering seal review beyond supplier shop drawings.

Please acknowledge this addendum as indicated in the Form of Tender.

**END OF ADDENDUM #2**

Yours truly,

A handwritten signature in blue ink, appearing to read "Heather M. Rossi".

Heather M. Rossi  
Procurement Specialist

**FORM OF TENDER – Appendix 1****SCHEDULE OF QUANTITIES AND PRICES**

(See paragraph 5.3.1 of the Instructions to Tenderers - Part II)

(All prices and *Quotations* including the *Contract Price* shall include all *Taxes*, but shall not include *GST*. *GST* shall be shown separately.)

Item	MMCD Ref.	Description	Unit	Quantity	Unit Price (\$)	Amount (\$)
<b>1</b>		<b><u>General Requirements</u></b>				
1.01		Mobilization and Demobilization	L.S.	1	\$	\$
1.02	01 57 01	Erosion & Sediment Control	L.S.	1	\$	\$
1.03		Start-Up & Commissioning	L.S.	1	\$	\$
1.04	01 33 01	O&M Manuals & Redline Drawings	L.S.	1	\$	\$
1.05		Contractor Design Temporary Bypass System	L.S.	1	\$	\$
1.06	01 55 00	Traffic Control	L.S.	1	\$	\$
1.07	01 53 01	Temporary Facilities	L.S.	1	\$	\$
1.08	01 58 01	Project Identification	INCIDENTAL			
1.09		Dewatering and Groundwater Treatment	INCIDENTAL			
<b>Subtotal Section 1 – to be carried over to summary page</b>					<b>\$</b>	

<b>2</b>		<b><u>Demolition and Removals</u></b>				
2.01		Removal and Disposal of Existing Pump Station Building	L.S.	1	\$	\$
2.02		Removal and Disposal of Existing Concrete	L.S.	1	\$	\$
<b>Subtotal Section 2 – to be carried over to summary page</b>					<b>\$</b>	

<b>3</b>		<b><u>Civil and Geotechnical</u></b>				
3.01		Pre-Locate Existing Utilities	L.S.	1	\$	\$
3.02	31 22 01	Site Grading & Restoration	L.S.	1	\$	\$
3.03	33 01 30.1	CCTV Inspection of Pipelines (Initial)	L.S.	1	\$	\$
3.04	33 01 30.1	CCTV Inspection of Pipelines (1 Year)	L.S.	1	\$	\$
3.03	33 34 01	Supply and Install Sanitary Forcemain	lin.m	85	\$	\$

Tenderer's Initials \_\_\_\_\_

Item	MMCD Ref.	Description	Unit	Quantity	Unit Price (\$)	Amount (\$)
3.06	33 11 01	Water Service and Associated Works	L.S.	1	\$	\$
3.07	32 14 01	Asphalt Parking Pad	L.S.	1	\$	\$
3.08	03 30 20	Rollover Curb and Sidewalk	lin.m	20	\$	\$
3.09	32 31 13	Supply and Install Perimeter Security Fence c/w Gate ( <i>Provisional</i> )	L.S.	1	\$	\$
<b>Subtotal Section 3 – to be carried over to summary page</b>					\$	

<b>4</b>						
<b><u>Pump Station Mechanical</u></b>						
4.01		Flygt Model 3127 LT 425 50Hz Sanitary Pumps	Each	2	\$	\$
4.02		Piping & Valves	L.S.	1	\$	\$
4.03		Metal Works	L.S.	1	\$	\$
<b>Subtotal Section 4 – to be carried over to summary page</b>					\$	

<b>5</b>						
<b><u>Pump Station Structural</u></b>						
5.01		Polyurethane Liner for Wet Well and Valve Chamber	L.S.	1	\$	\$
5.02	03 30 53	Cast-In-Place Wet Well and Valve Chamber Cover	L.S.	1	\$	\$
5.03	03 30 53	Cast-In-Place Concrete Pads	L.S.	1	\$	\$
5.04	03 30 53	Cast-In-Place Wet Well and Valve Chamber Walls, Floors and Benching	L.S.	1	\$	\$
<b>Subtotal Section 5 – to be carried over to summary page</b>					\$	

<b>6</b>						
<b><u>Pump Station Electrical</u></b>						
6.01		Electrical Service	L.S.	1	\$	\$
6.02		Standby Generator	L.S.	1	\$	\$
6.03		Electrical Kiosk	L.S.	1	\$	\$
6.04		Instrumentation	L.S.	1	\$	\$
6.05		SCADA Antenna and Assembly	L.S.	1	\$	\$
6.06		Electrical Systems	L.S.	1	\$	\$
6.07		4" Communication Conduit in Forcemain Trench	L.S.	1	\$	\$
<b>Subtotal Section 6 – to be carried over to summary page</b>					\$	

Tenderer's Initials \_\_\_\_\_

Item	MMCD Ref.	Description	Unit	Quantity	Unit Price (\$)	Amount (\$)
7		<b><u>Provisional</u></b>				
7.01		Alternate Forcemain Profile and Blow-Down Assembly	L.S.	1	\$	\$
7.02	31 23 17	Rock Removal	cu.m	20		
7.03	31 23 01	Over Excavation	cu.m	100		
7.04		Additional Cost for Removal and Disposal of Contaminated Materials in the Existing Pump Station Building <b><i>(Provisional)</i></b>			Allowance	\$15,000.00
<b>Subtotal Section 7 – to be carried over to summary page</b>					\$	

Tenderer's Initials \_\_\_\_\_

**FORM OF TENDER – Appendix 1****SCHEDULE OF QUANTITIES AND PRICES**

(See paragraph 5.3.1 of the Instructions to Tenderers - Part II)

(All prices and *Quotations* including the *Contract Price* shall include all *Taxes*, but shall not include *GST*. *GST* shall be shown separately.)

**TENDER SUMMARY**

<b>ITEM</b>	<b>DESCRIPTION</b>	<b>TOTAL AMOUNT</b>
1.0	General Items	\$
2.0	Civil and Geotechnical	\$
3.0	Pump Station Mechanical	\$
4.0	Pump Station Structural	\$
5.0	Pump Station Electrical	\$
6.0	Provisional	\$
TENDERED PRICE		\$
5% GST		\$
<b>TOTAL TENDERED PRICE</b>		<b>\$</b>

Tenderer's Initials \_\_\_\_\_