



# NEW WESTMINSTER

June 15, 2015

**ADDENDUM #4  
NWRFP-15-12  
Engineering Services,  
Twelfth Street Storm Sewer Outfall Reconstruction  
New Westminster, BC**

This addendum modifies the Request for Proposal only as noted:

**ADDITIONAL INFORMATION** (Answers to submitted questions)

- Q1 We have assumed that the outfall construction and associated works within the Fraser River may require approval from other agencies. Can you please confirm this and which agencies they are?
- A1 Agencies include, but not limited to, Port Metro, Department of Fisheries and Oceans, and Ministry of Environment.
- Q2 Will New Westminster look after all outside agency approval or will the consultant be responsible for this?
- A2 The Consultant will be responsible for the outside agencies.
- Q3 Can you please confirm if environmental consulting will be required (or is it being provided by the City)
- A3 The environmental consulting is to be part of the design team.
- Q4 Clause 8.1 states that part of storm sewer replacement includes “backwater valve”. Please define backwater valve required – does the City require another Tideflex Duckbill or can an alternate be considered?
- A4 The backwater valve will be an internal Tideflex valve or an approved equal. The Tideflex Duckbill valve will not be acceptable.
- Q5 Construction will severely impact the existing park facilities and access. What is required for restoration – complete restoration to existing standard? Interim standard restoration? No Restoration?
- A5 The City will remove the playground equipment we want to keep. After construction, the park will be left as level gravel area ready to be rebuilt under another contract. Back fill material above the pipe zone to be quality material. No construction material/spoils and contaminates will be allowed as backfill.

Q6 Does the City require installation of additional manholes on the existing storm sewer?

A6 This would be determined during design. We require manholes on either side of the internal Tideflex Valve. The access road from Quayside Drive will require a design for temporary road over top of the paving stones for protection. We will require tree protection layouts. Outfall pipe to be 1500 mm diameter

Please acknowledge this addendum in your Proposal.

**END OF ADDENDUM #4**

Yours truly,



Heather M. Rossi

Intermediate Buyer

email: [hrossi@newwestcity.ca](mailto:hrossi@newwestcity.ca)